

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

RECEIVED

OCT 15 2001

KCC WICHITA

WELL PLUGGING RECORD  
K.A.R.-82-3-117

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

API NUMBER 15-065-21-735-00-00

LEASE NAME Nicho1

WELL NUMBER 3

1650 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 15 TWP. 7 RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 1-83

Plugging Commenced 10-4-01

Plugging Completed 10-5-01

LEASE OPERATOR Production Drilling Inc.

ADDRESS P O Box 680

PHONE#(785) 625 1118 OPERATORS LICENSE NO. 5386

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-4-01 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? no logs

Producing Formation Toronto Depth to Top 3478-8 Bottom 3482 T.D. 3780

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	oil water	3478-82		8 5/8	250	0
				4 1/2	3780	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Ran tubing to 2000' Pumped 110 sx min con w/ 600# hulls. Cement cir.  
Pumped 30 bbls midcon down 8 5/8. SI  
10-5-01 Pumped 55 sx down 4 1/2 and 5 sx down 8 5/8 All pressured to 500# SI

Name of Plugging Contractor Production Drilling Inc. License No. 5386

Address P O Box 680 Hays Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Production Drilling Inc.

STATE OF Ks COUNTY OF Ellis, ss.

Aaron W. ... (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Aaron W. ...

(Address) P O Box 680 Hays Ks

SUBSCRIBED AND SWORN TO before me this 11th day of Oct, 192001

Deborah K. McKenna  
Notary Public

My Commission Expires:



OR