

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21544-00-02

LEASE NAME Davis #1

WELL NUMBER _____

SPOT LOCATION C NW NW

SEC. 15 TWP. 7s RGE. 22w (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 8/28/85

Plugging Completed 9/19/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lowell Moore Oil Co.

ADDRESS 609 S. Broadway, Plainville, Ks. 67663

PHONE # () 434-2543 OPERATORS LICENSE NO. 8618

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3860'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	385'	none
				4 1/2"	3858'	974'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bridge to 3350'. Pumped parafin down, sanded to 3450' & 5 sacks cement.
Shot pipe at 2804', 1995', 1502', 1198', & 974'. Pulled 24 joints of pipe.
Plugged well with 3 hulls, 30 gel, 100 cement mixed with 2 hulls, 10 gel, 8 5/8
plug, & 80 sacks 60/40 poz 6% gel 3% c.c.
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1985

My Commission expires: _____



Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
9/27/85
SEP 27 1985

CONSERVATION DIVISION
Wichita, Kansas