



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

6/5/75
RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Zenith Drilling Corp., Inc.

Complete Address Suite 600, 200 W. Douglas, Wichita, Kansas

Lease Name Schneider Well No. 1

Location NE SE NW Sec. 21 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3446'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8:45 P Day 2 Month 6 Year 1975

The above well was plugged as follows:

RTD 3446' 8 5/8 csg set 145' cwc 150 sk. Cmt. Mat. 60-40 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 150' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Masaryk
Well Plugging Supervisor

INVOICED

DATE 6/9/75

INV. NO. 1462-W