

15163-20505-0200

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1974
12/9/74
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1974
12/5/74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Zenith Drilling Corporation, Inc.

Complete Address Suite 600, 200 W. Douglas, Wichita, Kansas 67202

Lease Name Koppes Well No. 1

Location NE NW NE Sec. 21 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3422'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 10:45 A Day 3 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3422' 8 5/8 csg set at 204' cwc 150 sx.

5 1/2 csg set at 3408' cw 125 sk cem.

5 1/2 csg PBTB 3345' & pfs (3205-3326)

Filled 5 1/2 csg W/sd (3345-3175) dumped 5 sk cmt W/dump bailer. (3175-3140)

Cutoff and recovered 2600' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk 50-50 poz 6%.

-8 sk gel & water, released 8 5/8 plug & pumped 50 sk 50-50 poz 6% by HOWCO.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: B. J. Massey
Well Plugging Supervisor

DATE 12/10/74
INV. NO. 448-W