

15-163-20072-0080

Form CP-3
Rev. 6-26-62

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1967
10/30/67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Et Al, Inc.

Complete Address: 501 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name Schneider Well No. 1

Location C SW SE Sec. 21 Twp. 7 Rge. 19 (E) (W) X

County Rooks Total Depth 3440'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: E. K. Edmiston Drlg. Co.

Address: Wichita, Kansas License No.

Operation Completed: Hour 4 A Day 26 Month 10 Year 1967

The Above well was plugged as follows:

RTD 3440' 10 3/4 csg set at 238' cwc 185 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 100 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. Massey
Well Plugging Supervisor

DATE 10/30/67

INV. NO. 6578-W