

15-051-05323-00-00

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1962
Dec 17, 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Lease Name Richards Well No. 2

Location CW 1/2 SW NE Sec. Twp. 6 Rge. 11 (E) (W) 20

County Ellis Total Depth 3784

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kans License No. 457

Operation Completed: Hour 5PM Day 15 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 194' circulated with cement - 5 1/2" 3784' with 100 sax cement
Perf ? 5 1/2" squeezed at 780' with 100 sax cement.

Set plug at 3500', sand to 3450', set 4 sax cement with dump bailer,
started 510' 5 1/2" - circulated hole with heavy gel mud through 5 1/2"
at 510' - 15 sax gel - displaced 20 sax cement through 5 1/2" at 510'
heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180',
heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Lynch Co pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eddow Perry
Well Plugging Supervisor

DATE 12/17/62

INV. NO. 6235-W