

15-051-05321-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE NE SE

SEC. 6 TWP. 11 RGE. 20

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. ^{HEE 5.16.04} V-1 Lease Richards

Operator Veeder Supply & Dev Co Address Cherryvale, Kans

Field _____ County Ellis

Total Depth 3652 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3644' with 100

sax cement behind - Cement to 3620', perforated at 3525'

Sand to 3500', set 4 sax cement with dump bailer, pulled

2800' 5 1/2" - mud to 200', set rock and 20 sax cement, mud to

35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 01, 1955
NOV - 1 1955

CONSERVATION DIVISION
Wichita, Kansas

John Kelly
District Conservation Agent

Date 10-31-55

PLUGGING

FILE SEC 6 T 11 R 20W

BOOK PAGE 12 LINE 42