

15-051-00571-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 20-32

LOCATION NW-NW-SW

SEC. 6 TWP. 11 RGE. 20W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Schneider

Operator Imperial Oil & Gas of Kans. Inc. Address Wakeeney, Kansas.

Field _____ County Ellis.

Total Depth 3655' Feet.

Plugging Contractor Miller Casing Pulling Company.

Plugging Contractor's License No. 12

Address Box 711. Great Bend, Kansas.

(Describe Briefly the manner in which the well was plugged)

Surface pipe - 8 5/8" @ 250' c.w.c. 200 sx.

5 1/8" set @ 3629' cem. 100 sx.

Chat back to 3615' and 5 sx. cem. with dump bailer.

Shot 5 1/8" off @ 3030' and pulled same.

Squeezed with 25 sx. jell mud, H.O.W.C.O. plug and 100 sx. cem. to base of cellar.

Halliburton Oil Cem. Co. did the job.

Victor Schardt
District Conservation Agent

Date 6-25-57

PLUGGING
FILE SEC 6 T 11 R 20W
BOOK PAGE 20 LINE 32

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1957
JUN 28 1957
CONSERVATION DIVISION
Wichita, Kansas