

15-163-26507-00-8
08

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 12, 1973
NOV 1 2 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zenith Drilling Corporation

Complete Address 200 W Douglas, Wichita, Kansas

Lease Name Cooper Well No. 1

Location SE SE SE Sec. 14 Twp. 7 Rge. (E) (W) 20

County Rooks Total Depth 3513'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30 A Day 9 Month 11 Year 1973

The above well was plugged as follows:

RTD 3513' 8 5/8 csg set at 201' cwe 150 sx. Cem. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sx
cem thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 11/12/73
INV. NO. 8160-W