

DISTRICT CONSERVATION AGENT'S REPORT

*R*

15-163-00402-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SW NE

SEC. 14 TWP. 7 RGE. 20W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Cooper

Operator V. D. Sidey Oil Co Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3545 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 109' circulated with cement - 5 1/2" at 3540' with  
50 sax cement behind.

Filled with chat to 3520', set 5 sax cement with dump bailer,  
pulled 3180' 5 1/2", filled hole with mud to 150', set rock  
bridge and 15 sax cement, filled with mud to 35', set rock  
and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1951  
JUL 8 1951

*Edman Lee*  
District Conservation Agent

Date 7-28-51

**PLUGGING**  
FILE SEC 14 T 7 R 20W  
BOOK PAGE 99 LINE 18