

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NW

SEC. 14 TWP. 7 RGE. 20 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Burton

Operator W. L. Hartman Address 1501 54
Wichita, Kans

Field _____ County Rooks

Total Depth 5575 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 168' circulated with cement - 5 1/2" at 3532'

Lane wells plugs to 3382 - Perf. 3362 - Mud and chat to

3345 and 5 sax cement - Heavy mud to 168', wood plug, rock

and 15 sax cement - Heavy mud to 35', wood plug, rock and

10 sax cement

2900' 5 1/2" pulled

District Conservation Agent

Date 6-27-49

RECEIVED

CONSERVATION DIVISION

JUN 30 1949

JUN 30 1949

PLUGGING
FILE SEC 14 T 7 R 20 W
ROCK PAGE 103 LINE 76