

15-065-00311-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 23-9

LOCATION SW NW SW

SEC. 15 TWP. 7 RGE. 22W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Davis

Operator Lawrence Supply Co Address Box 448 Great Bend, Kans

Field _____ County Graham

Total Depth 3874 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 192' circulated with cement - 5 1/2" at 3850' with
50 sax cement behind - Baker plugs to 3700' - perforated at 3693'.
Filled with sand to 3680', set 4 sax cement with dump bailer,
pulled 1700' 5 1/2" - mud to 190', set rock and 15 sax cement, mud
to 40', set rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 12-16-55

PLUGGING
FILE SEC 15 T 7 R 22W
BOOK PAGE 23 LINE 9

12/22/55