

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20121-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1968
CONSERVATION DIVISION
Wichita, Kansas

2-26-68

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: P. O. Box #797, Great Bend, Kansas.

Lease Name Worcester Well No. 1

Location CE/2-SW-SW Sec. 10 Twp. 7 Rge. (E) (W)22

County Graham Total Depth 3225'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 10:30 AM Day 20 Month 2 Year 1968

The Above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated with 170 Sx.
Dakota section from 1020' to 1200'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru DP
from 1225' to 900'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215' to
155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. B. Nichols
Well Plugging Supervisor

DATE 2/26/68
INV. NO. 4326-W