

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1977
12-22-77
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - D05-20983-00-00 (of this well)
Lease Owner The Maurice L. Brown Co.
Address 200 Sutton Place Bldg., Wichita, Kansas 67202
Lease (Farm Name) Wilber Well No. 1
Well Location NE NW NW Sec. 8 Twp. 7S Rge. (R) 22 (W)
County Graham Total Depth 4010' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin December 16, 1977, 6:30 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Gerrell Veatch Address 38 Walnut Drive, Hill City, Ks. 67642
Plugging Contractor Abercrombie Drilling, Inc. License No. _____
Address 801 Union Center, Wichita, Kansas 67202
Invoice covering assessment for plugging this well should be sent to:
Name The Maurice L. Brown Co.
Address 200 Sutton Place Bldg., Wichita, Kansas 67202
and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Ass't. Sec.-Treas.
Date: December 20, 1977

15-065-20983-00-00

CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Wilbur #1
 LOCATION: NE NW NW Section 8-7S-22W
 Graham County, Kansas
 SPUD DATE: December 7, 1977
 COMPLETION DATE: December 16, 1977

0	270	Clay & sand
270	280	Blue shale
280	1060	Shale
1060	1850	Shale & sand
1850	1980	Shale
1980	2014	Anhydrite
2014	2730	Shale
2730	3380	Shale & lime
3380	3633	Lime & shale
3633	4010	Lime
	4010	Rotary Total Depth

Spud hole at 3:00 p.m., December 7, 1977. Drilled 280' of 12 1/4" hole. Ran 7 joints of 8-5/8" surface casing. Set at 279.55' K.B. with 200 sacks common cement, 3% CaCl, 2% gel. Plug was down at 10:00 p.m., December 7, 1977. Cement did circulate.

T.D. 4010'. Set 1st plug at 900' with 70 sacks, 2nd plug at 240' with 20 sacks, 40' solid bridge with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 6:30 a.m., December 16, 1977. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:
 Anhydrite 1980'
 B/Anhydrite 2014'

RECEIVED
 STATE CORPORATE COMMISSION
 DEC 22 1977
 CONSERVATION DIVISION
 Wichita, Kansas

12-22-77

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Wilbur #1, NE NW NW Section 8-7S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge,
 Assistant Secretary-Treasurer



Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 20th day of December, 1977.

Sandra Richman
 Sandra Richman, Notary Public

State of Kansas



15-065-20983-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

December 22, 1977

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Wilber
Description	NE NW NW Sec. 8-7-22W
County	Graham
Total Depth	4010
Plugging Contractor	Abercrombie Drilling, Inc.


The Maurice L. Brown Co.
200 Sutton Place
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above named well.