

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-005-00333-00-00

WELL PLUGGING APPLICATION FORM

Lease Owner Anschutz Drilling Co. Inc. Address 709 Union Nat'l Bk Bldg., Wichita, Ks.
(Applicant)
Lease (Farm Name) Gibb Well No. 1

Well Location NE NE NE Sec. 2 Twp. 7 Rge. 22(W)-(W)

County Graham Field Name (if any) _____

Total Depth 3885 Oil _____ Gas _____ Dry Hole X

Was well log filed with application? Yes. If not, explain: _____

Date and hour plugging is desired to begin June 11, 1952

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.
(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

Don Goheen Address Great Bend, Kansas

Name of Plugging Contractor Anschutz Drilling Company, Inc.

Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

Invoice covering assessment for plugging this well should be sent to Anschutz Drilling Co., Inc. Address 709 Union Nat'l Bk Bldg., Wichita, Ks. and payment will be guaranteed by applicant.

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1952
CONSERVATION DIVISION
Wichita, Kansas
6-21-1952

Don S. Miller
Applicant or Acting Agent

Date June 19, 1952

PLUGGING
FILE SEC 2 T 7 R W
BOOK PAGE 25 LINE 18

DRILLER'S LOG

Anschutz Drilling Company, Inc.
 #1 Gibb
 NE NE NE - 2-7S-22W
 Graham County, Kansas

<u>FROM</u>	<u>TO</u>	
0	40	Sand
40	190	Shale
190	830	Shalz & shells
830	865	Sand
865	890	Shale
890	1230	Shale & shells
1230	1260	Sand & shells
1260	1400	Shale & shells
1400	1415	Sand
1415	1440	Shale, shells & red rock
1440	1650	Sand
1650	1715	Shale, shells & red rock
1715	1900	Red bed & shale
1900	1930	Anhydrite
1930	2160	Shale & shells
2160	3525	Lime & shale
3525	3676	Lime
3676	3779	Lime & shale
3779	3845	Conglomerate
3845	3885	Arbuckle
	3885	TOTAL DEPTH
		D&A

COMMENCED: 5-30-52

COMPLETED: 6-11-52

CASING RECORD

Set 8-5/8" at 188 feet with 125 sacks cement and 1 sack calcium chloride.

ELEVATION: 2250 RB

TOPS

Topeka 3254 (-1004)
 Heebner 3465
 Toronto 3484
 Lansing 3502
 Base/Kansas City 3697
 Marmaton sand 3757
 Arbuckle 3835

DRILL STEM TEST

3614-36, open 1 hour, recovered 48 feet gas cut mud, no bottom hole pressure, closed 20 minutes

STATE OF KANSAS

COUNTY OF SEDGWICK

I hereby affirm that the foregoing is a true and correct copy of the log of Anschutz Drilling Company, Inc., #1 Gibb, located NE NE NE of Section 2-7S-22W, Graham County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *Leon L. Mehler*
 Leon L. Mehler

Subscribed and sworn to before me this 19th day of June, 1952.

 Notary Public

My commission expires: May 2, 1956.

PLUGGING
 FILE SEC 2 T 7 R 24
 PAGE 25 LINE 18

RECEIVED
 STATE OF KANSAS

6-21-52

CONSERTY



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-065-00333-00-00

June 21, 1952

Well No.	1
Lease	6136
Description	NE NE NE 2-7-22N
County	Graham
File No.	25-12

Laschritz Drilling Company, Inc.
709 Union Nat'l. Bank Bldg.
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 306, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR