

15-065-00062-00-00
WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE CORP
Give All Informa
Make Required A
Mail or Deliver I
Conservation
State Corpora
800 Bitting B
Wichita, Kans

15-065-00062-00-00

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines..... SE SE SE
County. Sec. 12 Twp. 7 Rge. (E) 21 (W)

Lease Owner. Appleman & Co.
Lease Name. Hibbett Well No. 1

Office Address. 120 Broadway New York, New York

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed. July 1 1947

Application for plugging filed. " 1 1947

Application for plugging approved. " 1 1947

Plugging commenced. " 1 1947

Plugging completed. " 1 1947

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....

Name of Conservation Agent who supervised plugging of this well..... H. W. Kerr Great Bend, Kansas

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	225	Cemented with 125 Sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

From 367 1/2' filled with 10 1/4" Mud to 200' Put in bridge and 15 sacks of Cement on Bridge filled with 10 1/4" Mud to 40' Put in Bridge and 10 Sacks of Cement on Bridge filling Hole to Base of Celler

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... N. Appleman
Address..... 120 Broadway New York, New York

STATE OF....., COUNTY OF....., SS.

..... (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VEEDER SUPPLY & DEVELOPMENT CO.

(Signature)..... Samuel Veeder
PRESIDENT

Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of July 1947

Lois Louard
Notary Public.

My commission expires 7-11-48



Veeder Supply & Dev'l. Co.

15-865-00062000

Cherryvale, Kansas

Drilled for N. APPLEMAN Farm HIBBITT No. 1 Depth 3674
 Contractor VEEDER SUPPLY & DEV'L. CO. Pipe 227' of 8 5/8 Csg. Cemented with 125 sacks
 Location Sw SW SW Sec. 12 Twp. 7 Range 21
 Commenced 6-14-47 Completed 7-1-47 County Graham State Kansas

Soap Stone	0	80	80
Sand Shale	80	215	135
Shale	215	278	63
Sand	278	370	92
Shale blue	370	580	210
Sandy shale	580	680	100
Sand Shale, Shells	680	1205	525
Sand Shale	1205	1350	145
Sand	1350	1475	125
Shale	1475	1760	285
Anhydrite	1760	1810	50
Shale	1810	1855	45
Shale shells	1855	2535	680
Lime shale	2535	2555	20
Shale shells	2555	2730	175
Lime shale	2730	2895	165
Shale shells	2895	3005	110
Lime shale	3005	3255	250
Lime	3255	3285	30
Lime shale	3285	3335	50
Lime	3335	3616	281
Cong.	3616	3638	22
Sand	3638	3666	28
Quartzite	3666	3674	8
Total Depth	3674		

AFFIDAVIT

STATE OF KANSAS

MONTGOMERY COUNTY SS:

EMMETT C. VEEDER, of lawful age, being duly and solemnly sworn on oath says;

I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the Hibbitt # 1 Well in Section 12-7-21 Graham County, Kansas, is true and correct.

Further affiant saith not.

THE VEEDER SUPPLY & DEV'L. CO.

BY Emmett C. Veeder
President

Subscribed and sworn to before me this 7 th day of July 1947.

Lee L. Conrad
Notary Public

My Commission Expires: 7-11-48