

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23278-00-00  
Spot: NWSENWNE Sec/Twnshp/Rge: 30-11S-20W  
800 feet from N Section Line, 1840 feet from E Section Line  
Lease Name: LYND Well #: 1  
County: ELLIS Total Vertical Depth: 3950 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

PROD Size: 4.5 feet: 3900  
SURF Size: 8.625 feet: 250

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2005 3:30 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Casing parted.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/22/2005 4:45 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

**Perfs:**

Poe Well Service drilled on well with mud pump and swivel to 1100' - got metal shavings and red sand.  
Pulled tubing to remove bit.  
Ran back into hole to 1050' and pumped 50 sxs 60/40 pozmix to circulate cement out of 4 1/2" casing.  
Pulled tubing - tied onto 4 1/2" casing with a swedge - pumped 10 sxs 60/40 pozmix with 50# hulls mixed in.  
Max. P.S.I. 600#. S.I.P. 500#.  
Tied onto 8 5/8" casing - pumped 40 sxs 60/40 pozmix.  
Max. P.S.I. 500#. S.I.P. 500#.

Remarks: ALLIED CEMENTING COMPANY-TICKET #21515.

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

RECEIVED

JUN 27 2005

KCC WICHITA

JUN 23 2005

Expired 6-30-86

replacement card

I & R EXPLORATION  
HAYSKS

30-11S-20W  
800'FNL & 1840'FEL, SEC

#1 LYND

site: 8-3/4 N & 1/2 W OF ELLISKS

cty: ELLIS

API 15-051-23278

contr: JOHN O FARMER

field: NICHOLSON

geol: PAUL MONTOJA

fr date 12/08/82      spd date 12/15/82      drig comp 12/21/82      card issued 04/14/83      last revised 01/20/97


ELV: 2270 KB, 2265 GL LOG	tops.....depth/datum
ANH.....	1685 + 585
TOP.....	3302 - 1032
HEEB.....	3521 - 1251
TOR.....	3544 - 1274
LANS.....	3558 - 1288
BKC.....	3787 - 1517
MARM.....	3820 - 1550
CONG.....	3852 - 1582
ARB.....	3890 - 1620
RTD.....	3950 - 1680

**IP status:**  
**OIL, P 12 BO & 40 BWP, LKC, INTV NA , (NEW PAY)**  
**, 03/01/83**  
 CORR & INFO REL: 1/20/97 - CORR TOPS, WAS TEMP  
 COMP  
 CSG: 8-5/8" 250, 4-1/2" 3900  
 NO CORES OR DSTS RPTD  
 MICT - CO, PF (PENN BASAL SD). TRTMNT NOT  
 RPTD, SLI SO, FORMATION TITE, PB (DEPTH NA), PF  
 (LKC) INTV NA, AC'D, SO, POP, P 12 BO & 40 BWP,  
 3/1/83 (NEW PAY) - NO OTHER INFO RELEASED BY  
 OPERATOR OR ON KCC RECORDS; ALL REQUESTS  
 FOR INFO DENIED

COPYRIGHT 1997  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS