

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20198-00-00
Spot: E2SESE Sec/Twnshp/Rge: 12-5S-22W
660 feet from S Section Line, 330 feet from E Section Line
Lease Name: BITTEL Well #: 3
County: NORTON Total Vertical Depth: 3476 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

PROD Size: 4.5 feet: 3474 100 SX CMT
SURF Size: 8.625 feet: 200 200 SX CMT

112 97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2005 9:00 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered out 250 sxs Swift Multi-Density Cement and 500# hulls.
Top tubing-fish 2045'. 2 3/8" with packer on bottom left in hole.
No squeeze returns - perforate Anhy 1680'. Base Dakota at 950'.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/28/2005 2:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Perforated Anhy at 1680' and Base Dakota 950'.
Ran tubing to 1951'. Swift Services pumped 125 sxs Swift Multi-Density cement with 350# hulls - cement circulated.
PTOH. Swift pumped 75 sxs SMD with 150# hulls.
Max. P.S.I. 700#. S.I.P. 200#.
Shut in one hour - cement fell back - topped off with 18 sxs cement.
Hooked up to 8 5/8" - pumped 7 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

6-30-05

INV. NO.

2005061870

RECEIVED

JUN 30 2005

KCC WICHITA

JUN 29 2005

R P NIXON OPERATIONS
207 W 12TH

#3 BITTEL

12-5-22W
C E/2 SE SE

HAYS, KS 67601

CONTR JAY-LAN CORP

CTY NORTON

GEOLOGIC DAN NIXON

FIELD DENSMORE

E 2050 KB CM 11/20/80 CARD ISSUED

4/16/81 IP

P 15 BOPD & NW

API 15-137-20,198

REAG OH 3474-76

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
KC		3221	-1171
REAG		3472	-1422
RTD		3476	-1426
NO LOG			

8-5/8" 200, 4 1/2" 3474/100sx

NO DST'S REPORTED
MICT - CO, (REAG OH), SWB DWN &
REC 4 BOPH, NW, NAT, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS