

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20268-00-00
Spot: SESWSW Sec/Twnshp/Rge: 12-10S-24W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SE GANO UNIT Well #: 2-7
County: GRAHAM Total Vertical Depth: 4100 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 4.5 feet: 4098 250 SX CMT
SURF Size: 8.625 feet: 215 150 SX CMT

\$133²⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2005 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 250 sxs Swift Multi-Density Cement and 600# hulls.
Top of tubing fish 3117'.
No squeeze records: perforate 1275' and 2140'.
PBSD 4070'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/15/2005 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated at 1275' and 2140'.
Swift Services pumped 50 sxs SMD neat, followed with 120 sxs SMD with 600# hulls.
Max. P.S.I. 400#. S.I.P. 50#.
Hooked up to backside and pumped 35 sxs SMD.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3834	4032		
3820	3828		
3576	3584		

Remarks: LEASE ORIGINALLY KNOWN AS BEESLEY #7. SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

RD

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

RECEIVED

DATE

6-30-05

JUN 30 2005

TRK. NO.

2005061873

JUN 16 2005

KCC WICHITA

WICHITA
 INDEX

DON E. PRATT #7 BEESLEY 12-10-24W
 HAYS, KS. SE SW SW
 Contr. HELBERT DRUG. COMPANY City. GRAHAM
 Geol. Pool GANO SE
 E. 2493 KB Cm. 10/10/69 Cp. 12/24/69 IP PMP 70 BOPD +50%
 W, GR 38/LANS 3874-78
 API 15-065-20,268

LOG Tops	Depth	Datum	Csg.
			8-5/8" 212/150 SX
			4 1/2" 4098/250 SX
ANH	2114	+ 379	DST 3828-3900/60", 900' O&GCSW, BHP 1268-1245#/30", FP 83- 481# CO & PF (LKC) 20/4004-09, A 250, SWB LD, NO SHO, A 750; SWB DN, SO (SHORT 18 BL) A 300 CRA, SWB DN, FL LEVEL 1900', SWB 16 BFPH, 20% OIL N/T, BP 3996; PF (LKC) 16/ 3874-78; NO TST NAT, A 250, SWB LD & SWB 1 1/2 BOPH N/T, A 1500, SWB LD & SWB 25 BFPH, 50% OIL, N/T, NO CORES
B ANH	2149	+ 344	
TOP	3576	-1083	
HEEB	3794	-1301	
TOR	3820	-1327	
LANS	3833	-1340	
BKC	4060	-1567	
RTD	4100	-1607	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS