

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24703-00-00
Spot: SWNESW Sec/Twnshp/Rge: 31-12S-20W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HUBER B Well #: 9
County: ELLIS Total Vertical Depth: 3950 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3849 w/175 sxs cmt
SURF Size: 8.625 feet: 209 w/140 sxs cmt

#12838

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2005 12:35 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TERRY PIESKER Company: GLM COMPANY Phone: (785) 735-4363

Proposed Plugging Method: Ordered 330 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV tool at 1577'. Fluid level 1880'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2005 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing tied onto 5 1/2" casing with a swedge and pumped 280 sxs 60/40 pozmix - 10% cement with 450# hulls mixed in.
Max. P.S.I. 200#. S.I.P. 50#.
Tied onto 8 5/8" and pumped two barrels with Max. P.S.I. 400#. S.I.P. 400#.
Will cut off and top if needed.


Perfs:

Top	Bot	Thru	Comments
3861	3863		
3854	3856		
3844	3846		
3352	3354		
3259	3262		

Remarks: LEASE ORIGINALLY KNOWN AS HUBER B-5-CHANGED TO HUBER B-9-09/20/2001-SEE RBDMS WELL COMMENTS. ALLIED CEMENTING COMPANY-TICKET #21532.

Plugged through: CSG

District: 04

Signed  (TECHNICIAN)

RECEIVED

JUL 05 2005

KCC WICHITA

INVOICED

DATE 7-5-05

TW. NO. 2006060013

Form CP-2/3

JUN 30 2005

STATE KANS COUNTY ELLIS
 FIELD ELLIS (MULTIPAY)
 OPER AFG ENERGY
 WELL 9 HUBER "B" *See Well Comments RBOMS.*
 API 15-051-24703-0000
 SPUD 10/29/1990
 DTD 3950 LTD FTD ARBUCKLE

WELL CLASS DO
 STATUS OIL
 COMP 12/05/1990
 PSTD

31-12S-20W
 SW NE SW
 1650FSL 3630FEL SEC



LOC 1 1/2 MI NW ELLIS, KS

Petroleum Information Corporation

IPP 15 BOPD 50 BW
 PROD ZONE: ARBUCKLE 3870-3894 GROSS

EL: 2213 KB 2208 GR

CSGS: 8 5/8 @ 209 W/ 140 SACKS
 5 1/2 @ 3849 W/ 175 SACKS
 DV TOOL @ 1562
 PERF FOR SQZ 3903-3905. SQZD W/100 SX.
 PERF FOR SQZ 3893-3895. SQZD W/CMT.
 PERF FOR SQZ 3872-3874. SQZD W/100 SX.

TBGS: 2 7/8 @ 3895
 DRLG COMP 11/3/90 RIG REL 11/4/90

DSTS: DST 1 3852-3863 ARBUCKLE
 REC 120 FT GAS 65 FT OIL 75 FT MCO
 INIT OP 30M IFF 10 FFP 31

PERFS: ARBUCKLE PERF W/ 4/FT 3870-3894 GROSS: 3870-3873 3890-3894
 ACID 500 GALS FBRKP 150
 RATE 1.0B/MIN ATP 200

CONTR: EMPHASIS OIL OPER RIG# 8

NO CORES
 GEOL: STEVE PARKER

LOG TOPS:
 ANHYDRITE 1558 +655
 BSE ANHYDRITE 1598 +615
 TOPEKA 3229 -1016
 HEEBNER 3453 -1240
 TORONTO 3475 -1262
 LSG-KANSAS CITY 3490 -1277
 BSE LSG-KS CITY 3733 -1520
 MARMATON 3770 -1557
 ARBUCKLE 3838 -1625
 TD 3950 -1737

LOG TYPES: GR CNL CBL

KS 4-010191

Copyright 1991 Petroleum Information Corporation