

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01858-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 16-10S-18W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BEMIS Well #: 1
County: ROOKS Total Vertical Depth: 3590 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3589 200 SX CMT
SURF Size: 8.625 feet: 159 150 SX CMT

68
\$ 116

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2005 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: GLM COMPANY Phone: (785) 735-4363

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing leaks. Tubing and rods stuck in the hole at 3200'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2005 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2950'.
Allied rigged onto tubing and pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 2000' - pumped 70 sxs cement with 100# hulls mixed in.
Pulled tubing to 1000' - pumped 85 sxs cement with 100# hulls mixed in to circulate cement to surface.
Pulled tubing - tied onto 5 1/2" casing - pumped 10 sxs cement.
Max. P.S.I. 350#. S.I.P. 100#.
Tied onto 8 5/8" casing - pumped 85 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3461	3466		
3453	3459		
3432	3440		
3290	3295		

Remarks: ALLIED CEMENTING COMPANY-TICKET #21531.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

JUL 05 2005

KCC WICHITA

INVOICED

DATE

7-5-05

TRW. NO.

2006060013

JUN 30 2005

BARNETT OIL CO #1 BEMIS 16-10-18W
 NW NW SE
 Contr. _____ ROOKS County
 E 2175RB Comm. _____ Comp. 9-30-55 IP 110 BOPD

Tops	Depth	Datum
ANH	1555	620
TOP	3141	-966
HEEB	3357	-1182
TOR	3373	-1198
KC	3397	-1222
TD	3590	-1415

Casing
 8" 159
 5" 3589
 DST 3364-85/1 1/2 HR, 60' OCM
 BHP 610#: DST 3421-43/1 HR,
 30' O & GCM, 60' OCM, BHP
 380#: DST 3520-44/1 HR, 90'
 OCM, 60' OC MDY WTR, BHP 990#
 DST 3553-80/1 HR, 15' MUD,
 RAINBOW SO, BHP 250#: PERF
 WILLIAMS SE 24/3453-59: 12/
 3461-66: ACID 500
 PLUG: PERF 3432-40
 &WB 13 BO/5 HR:

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS