

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22604-00-00
Spot: SWSESE Sec/Twnshp/Rge: 29-33S-13W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: SPRIGGS H Well #: 1
County: BARBER Total Vertical Depth: 4352 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

CIBP Size: feet: 3925 WITH 2 SX CMT
PROD Size: 4.5 feet: 4345 WITH 150 SX CMT
SURF Size: 10.75 feet: 255 WITH 200 SX CMT

#141 44

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/20/2005 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 3925' WITH 2 SX CMT. PLUG AT 600' WITH GEL & 50 SX CMT. PLUG AT 290' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2005 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3925' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3966	3976		

INVOICED
DATE 6-29-05
INV. NO. 2005061868

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3450' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JUN 29 2005
KCC WICHITA

[Signature]