

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-20417-00-00  
Spot: SWSWSWNE Sec/Twnshp/Rge: 3-27S-35W  
2540 feet from N Section Line, 2340 feet from E Section Line  
Lease Name: DEW A Well #: 2  
County: GRANT Total Vertical Depth: 3050 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: 5 E. GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

CIBP Size: feet: 2790 WITH 2 SX CMT  
PROD Size: 4.5 feet: 3049 WITH 225 SX CMT  
SURF Size: 8.625 feet: 796 WITH 400 SX CMT **# 99'13**

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2005 9:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2790' WITH 2 SX CMT. MUD SPACER TO 1900' WITH 15 SX CMT. PLUG AT 825' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/23/2005 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 2790' WITH 2 SX CMT ON TOP. 1ST PLUG PUMP MUD SPACER & 15 SX CMT AT 1900'. 2ND PLUG PULL OUT OF HOLE TO 825'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2882	2892		
2866	2878		
2856	2862		
2842	2852		
2836	2840		
2005			TOC

**INVOICED**  
DATE 6-30-05  
SER. NO. 2005061874

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1097' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

RECEIVED  
JUN 30 2005  
KCC WICHITA

Form CF 23