

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20758-00-00
Spot: NESE Sec/Twnshp/Rge: 17-22S-35W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: BOPP Well #: 3-17
County: KEARNY Total Vertical Depth: 4650 feet

Operator License No.: 3716
Op Name: B & G PRODUCTION, INC.
Address: PO BOX 427
BOOKER, TX 79005

PROD Size: 5.5 feet: 4646 WITH 270 SX CMT
SURF Size: 8.625 feet: 398 WITH 250 SX CMT

#151¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2005 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT AT 4200' THROUGH TBG. PLUG AT 2000' WITH 50 SX CMT. PLUG AT 950' WITH 15 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/17/2005 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 20 SX CMT & 200# HULLS IN 5 1/2" CASING AT 4200' SPOTTED THROUGH TUBING. PULL TUBING TO 1400' & CIRCULATE MUD TO SURFACE. 1ST PLUG AT 2000' WITH 50 SX CMT THROUGH TUBING. NO CIRCULATION. TAGGED CMT PLUG AT 2421'. 2ND PLUG LOAD HOLE WITH MUD. SPOT 50 SX CMT AT 2000' THROUGH TUBING. FULL RETURNS. 3RD PLUG SPOT 15 SX CMT AT 950' THROUGH TUBING. FULL RETURNS. 4TH PLUG SPOT 50 SX CMT AT 400' THROUGH 5 1/2" CASING. 5TH PLUG SPOT 10 SX CMT AT 40' THROUGH 5 1/2" CASING.

Perfs:


Top	Bot	Thru	Comments
4514	4522		

INVOICED
DATE 7-5-05
TRV. NO. 2006060005

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 568' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
JUL 05 2005
KCC WICHITA

Form CH 2/3