

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20557-00-01
Spot: NESENE Sec/Twnshp/Rge: 34-31S-4E
3631 feet from S Section Line, 462 feet from E Section Line
Lease Name: E L MORRIS Well #: 8
County: COWLEY Total Vertical Depth: 3416 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3409 65 SX CMT
SURF Size: 8.625 feet: 199 100 SX CMT

111⁰²

Well Type: EOR UIC Docket No: E27204.1 Date/Time to Plug: 06/02/2005 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 06/02/2005 4:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded bottom from 3415' to 3340'; dump bailed 5 sacks of cement; and POOH 515' with 5-1/2" casing. Top plug RIH with tubing at 250' and circulated 100 sacks of 60/40 posmix with 4% gel to surface.

Copeland #25363

Perfs:

Top	Bot	Thru	Comments
3413	3415		
394	395		

RECEIVED
KCC DISTRICT #2
JUN 27 2005
WICHITA, KS

Remarks: OBSERVED TOP PLUG

Plugged through: TBG

District: 02

Signed

Duane R. Krueger

(TECHNICIAN)

RECEIVED
JUL 05 2005
KCC WICHITA

INVOICED
DATE 7.5.05
INV. NO. 2006060007