

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00255-00-01
Spot: SE Sec/Twnshp/Rge: 26-22S-32W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: OLDWEILER UNIT OWWO Well #: 1
County: FINNEY Total Vertical Depth: 2750 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVENUE - SUITE 2350
OKLAHOMA CITY, OK 73102

PROD Size: 5.5 feet: 2749 750 SX CMT
SURF Size: 8.625 feet: 209 175 SX CMT
89 38

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/20/2005 8:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & 400# HULLS. MUD SPACER & 25 SX CMT AT 2000'. MUD SPACER & 25 SX CMT AT 1300'. MUD SPACER & 25 SX CMT AT 650'. MUD SPACER & 30 SX CMT FROM 240' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2005 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 300# HULLS AT 2728'. 1ST PLUG PUMP MUD SPACER & 25 SX CMT AT 2000'. 2ND PLUG PUMP MUD SPACER & 25 SX CMT AT 1300'. 3RD PLUG PUMP MUD SPACER & 25 SX CMT AT 650'. 4TH PLUG PUMP MUD SPACER & 30 SX CMT AT 240-0'. PRESSURED 5 1/2" CASING TO 400#. HELD. 5 1/2" X 8 5/8" ANNULUS FULL OF CMT TO SURFACE.


Perfs:

Top	Bot	Thru	Comments
2723	2728		
2690	2698		

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED, 5 1/2" CEMENTED TO SURFACE.

Plugged through: CSG

District: 01



Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
JUL 05 2005
KCC WIC/UIT

INVOICED
DATE 7-5-05
2006060016