

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23071-00-00  
Spot: NESESW Sec/Twnshp/Rge: 2-8S-21W  
950 feet from S Section Line, 2510 feet from W Section Line  
Lease Name: NUTSCH BENOIT Well #: 1-2  
County: GRAHAM Total Vertical Depth: 3550 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W. MAIN - PO BOX 428  
LOGAN, KS 67646

SURF Size: 8.625 feet: 218

A 115<sup>38</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2005 1:30 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE  
Date/Time Plugging Completed: 06/28/2005 3:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3530' w/25 sxs.  
2nd. Plug at 1600' w/25 sxs.  
3rd. Plug at 825' w/100 sxs.  
4th. Plug at 275' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 

(TECHNICIAN)

RECEIVED

JUL 05 2005

KCC WICHITA

INVOICED

DATE

7.5.05

INV. NO.

2006060006

Form CP-2/3

JUN 30 2005