

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23044-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 2-7S-21W
400 feet from N Section Line, 2310 feet from E Section Line
Lease Name: KENNETH Well #: 1
County: GRAHAM Total Vertical Depth: 3800 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

SURF Size: 8.625 feet: 238

\$ 123⁵⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/22/2005 1:00 AM
Plug Co. License No.: 9292 Plug Co. Name: SCHECK, TIMOTHY DBA SCHECK OIL OPERATION
Proposal Rcvd. from: STAN LOVELADY-BIG THR Company: GREAT EASTERN ENERGY & DEV. Phone: (432) 682-1178

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES WitnessType: NONE
Date/Time Plugging Completed: 06/22/2005 2:15 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

1st. Plug at 3765' w/25 sxs.
2nd. Plug at 1890' w/25 sxs.
3rd. Plug at 1070' w/100 sxs.
4th. Plug at 288' w/40 sxs.
5th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Regu L Moses
(TECHNICIAN)

RECEIVED
JUL 05 2005
KCC WICHITA

INVOICED
DATE 7.5.05
INV. NO. 2006060010

Form CP-2/3

JUN 29 2005