

15-065-21880-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: -15-065-21880-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 15-7S-22W
1060 feet from S Section Line, 1000 feet from E Section Line
Lease/Unit Name: NICHOL Well Number: 4-A
County: GRAHAM Total Vertical Depth: 3787 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: PO BOX 680
HAYS, KS 67601

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.62 feet: 247 175 SX CMT
Production: Size 5.5 feet: 3781 175 SX CMT
Liner: Size _____ feet: _____
123.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2000 11:00 AM
Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1189

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Elevation 2270'. Fluid level 300' from surface.
PBTD 3781'. Perfs 3483' - 3756'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/20/2000 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:
Perforated 2 shots 1910' and 2 shots at 1120'. Fluid level at 300'.
Ran tubing to 2741'. Allied pumped 150 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled tubing to 1395'. Allied pumped 90 sxs - circulated cement.
PTOH and squeezed with 60 sxs.
Max. P.S.I. 500#. S.I.P. 250#.
Pumped 50 sxs with 200# hulls down backside 0#.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 26 2000
12/26/00
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 04 Signed *Richard Williams*
(TECHNICIAN)

INVOICED
DATE 12/27/00
INV. NO. 2001061194
DEC 21 2000
Form CP-2/3

replacement card

RON'S OIL OPER
PENOKEE KS 67659

15-07S-22W
1060'FSL & 1000'FEL, SEC

4 NICHOL A

site: 4-3/4 N & 4-1/4 E OF HILL CITY KS
contr: HELBERG OIL

cy: GRAHAM
field: WORCESTER

API 15-065-21880

geol:
fr date 10/18/83 spd date 10/27/83 drig comp 11/06/83 card issued 03/01/84 last revised 01/20/97

ELV: 2275 KB, 2270 GL
tops.....depth/datum
RTD.....3787 -1512
NO TOPS RPTD

IP status:
OIL, P 20 BOPD, NW, LKC 3484-3488, MARM 3654-3656
, ARB 3781-3787, 11/21/73
INFO RELEASED: 1/20/97 - WAS TEMP COMP
CSG: 8-5/8" 247 / 175 SX, 5-1/2" 3781 / 175 SX
SHOWS: SO IN TOR
DRLR SD ZNS: 0-1899 (W/SH)
NO CORES OR DSTS
MICT - CO, (ARB OH), SO, NAT, PF (MARM) 3654-3656,
W / 4 SPF, AC 500 GAL, SO, PF (LKC) 3484-3488, W / 4
SPF, AC 300 GAL, SO, SET 2" TBG AT 3781, NO PKR,
POP, IPP 20 BOPD, NW (GR 35), 11/21/83,
COMMINGLED - NO OTHER INFO AVAILABLE ON
KCC RECORDS

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS