

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21735-00-00
Spot: CS2N2SE Sec/Twnshp/Rge: 15-7S-22W
1650 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: NICHOL Well Number: 3
County: GRAHAM Total Vertical Depth: 3800 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: PO BOX 680
HAYS, KS 67601

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 250 175 SX CMT
Production: Size 4.5 feet: 3798 175 SX CMT 9/23.50
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2001 12:00 PM

Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.

Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1118

Proposed Port collar at 1900'.
Plugging Casing leak at 1850'.
Method: Perfs 3478' - 3482'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/05/2001 9:00 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2000' - Swift pumped 110 sxs of Swift Multi-Density cement with 500# hulls - cement circulated.
PTOH.
10-05-2001 - Hooked up to backside and pmped 30 sxs - 0# - out of cement.
10-05-2001 - Cement fell back 1000'. Swift pumped 35 sxs Swift Multi-Density cement.
Max. P.S.I. 500#. S.I.P. 500#.
10-05-2001 - Pumped 5 sxs down backside - pressured up to 500#.

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

INVOICED

Form CP-2/3

OCT 16 2001

DATE 10-16-01

OCT 15 2001

KCC WICHITA

INV. NO. 2002060811

RON'S OIL OPERATIONS, INC.

REPLACEMENT CARD

15-7-22W

RT. #1, BOX 76

#3 "A" NICHOL

C S/2 N/2 SE

HILL CITY, KS 67642

CONTR SANTA FE DRILLING

CTY GRAHAM

GEOL PAUL MONTOIA

FIELD WORCESTER

+	+	+
+	+	+
+	+	+

ELV 2271 KB SPD 12/11/82 CARD ISSUED 4/14/83

IP P 52 BO & 2 BWPD

2261 GL

SHAW (TOR) 347B-3482

API 15-065-21,735

LOG	Tops	Depth	Datum
ANH	1868 +	403	
B/ ANH	1898 +	373	
TOP	3268 -	997	
TOR	3453 -	1182	
LKC	3477 -	1206	
BKC	3496 -	1225	
SIMP SD	3755 -	1484	
RTD	3800 -	1529	

8 5/8 " 250/175SX; 4 1/2 " 3798/175SX; DV TOOL (PORK COL-LAR) AT 1100
 DST (1) 3461-90 (TOR) / 30-45-45-90, SB TO, 350' GIP, REC 60' OIL, 90' OCM (50% OIL, 50% M), 120' OCM (45' OIL, 55% M), 60' OCM (30% OIL, 70% M), SIP 229-240#, FP 65-120 / 141-163#, HP 1738-1696#
 DST (2) 3553-75 (LKC) / 30-30-30-30, (1ST OP) WB 20", (2ND OP) NB, REC 20' M, W / OIL SPTS, SIP 651-565#, FP 54-54 / 54-54#, HP 1843-1822#
 MICT - CO, PF (SIMP SD) 3754-59 W/4 SPF, SWB DWN & REC 7 BWPH, NAT, SET BP, PF (PENN) 3674-79 W/4 SPF, AC 1500G, SWB LD, NON-COMMERCIAL, PF (TOR) 3478-82 W/4 SPF, AC 300G (15%), SWB DWN & REC 4 BUPH, NW: 6 HRS, SET 2" TBG AT 3790', POP, P 52 BO & 2 BWPD, 1/19/83

CORRECTION: 6/23/83 - CORRECTED TOPS & WELL INFO

INDEPENDENT OIL & GAS SERVICE
WICHITA KANSAS

W 1010 E