

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21395-00-00  
Spot: CN2SWSE Sec/Twnshp/Rge: 15-7S-22W  
990 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: NICHOL Well Number: 1  
County: GRAHAM Total Vertical Depth: 3829 feet

Operator License No.: 5386  
Op Name: PRODUCTION DRILLING, INC.  
Address: PO BOX 680  
HAYS, KS 67601

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 250  
Production: Size 4.5 feet: 3824  
Liner: Size feet:

*3/24.44*

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/04/2001 9:00 AM

Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.

Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1118

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/05/2001 10:00 AM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perforated 1175' and 1950'.  
Swift Services pumped 120 sxs Swift Multi-Density with 400# hulls.  
Max. P.S.I. 200#. S.I.P. 0#.  
Hooked up to backside and pumped 30 sxs with 200# hulls.  
Max. P.S.I. 150#. S.I.P. 0#.  
10-05-2001 - Cement down 1000'. Swift pumped 35 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.  
10-05-2001 - Backside on vacuum. Swift pumped 20 sxs cement.  
S.I.P. 300#.

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

RECEIVED

OCT 16 2001

KCC WICHITA

INVOICED

DATE 10-16-01

INV. NO. 200206086

Form CP-2/3

OCT 15 2001

*10/16/01*

NICKELSON OIL OPERATIONS  
RT 1, BOX 76

#1 NICHOL

15-7-22W  
C N/2 SW SE

HILL CITY, KS 67642  
CONTR LAWBANCO, INC.

CTY GRAHAM

GEOL PAUL MONTOIA FIELD WC (3/8 W OF WORCESTER;  
OVER 1/2 FROM PROD)

E 2304 KB CM 3/24/81 CARD ISSUED 10/1/81 IP P 10 BOPD & NW  
ARB OH 3824-3829  
API 15-065-21, 395 SHAW(TOR) P 92 BO & 13 BWPD  
3515-3519

LOG	TOPS	DEPTH	DATUM
ANH		1926	+ 378
TOP		3215	- 911
HEEB		3489	-1185
TOR		3514	-1210
LKC		3530	-1226
B-KC		3724	-1420
ARB		3818	-1514
RTD		3829	-1525

8 5/8" 250; 4 1/2" 3824  
DST (1) 3521-55(TOR-LKC)/30-60-30-60  
340' GIP, REC 10' VSOCM, SIP  
54-32#, FP 75-32/43-32#  
HP 1923-1852#  
DST (2) 3545-90(LKC)/30-30-30-60,  
51' OIL SPKD MW, 2460' MSW, SIP  
1260-1226#, FP 323-919/990-1157#  
HP 1914-1865#  
DST (3) 3684-3725(LKC)/30-60-15-15,  
30' OIL SPKD M, SIP 1256-1118#  
FP 50-40/70-60#, HP 1983-1863#  
MICT - CO, (ARB OH), SWB SO, NAT, POP  
P 10 BOPD, NW 4/26/81, OFF PMP, PF  
(TOR) 3515-19, SWB GSO, NAT, POP, P  
92 BO & 13 BWPD 9/9/81, COMMINGLED

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS