

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22471-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 2-34S-13W
990 feet from S Section Line, 2410 feet from E Section Line
Lease Name: MOTT D Well #: 2
County: BARBER Total Vertical Depth: 3649 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

PROD Size: 4.5 feet: 3648 WITH 110 SX CMT
SURF Size: 8.625 feet: 344 200 SX, 2% GEL, 3% cc

118⁵⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2005 8:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK TO 3590' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2005 9:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3590' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3641	3644		

INVOICED
DATE 6-21-05
INV. NO. 2005061839

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Peifer
(TECHNICIAN)

RECEIVED
JUN 21 2005
KCC WICHITA

Form 11/3