

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22457-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 11-34S-13W  
330 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: DONOVAN H Well #: 1  
County: BARBER Total Vertical Depth: 3677 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

PROD Size: 4.5 feet: 3674 WITH 110 SX CMT  
SURF Size: 8.625 feet: 356 200 SX, 2% GEL, 3% CC

*#11950*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2005 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK TO 3620' & 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/07/2005 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3620' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PUMP DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 200#.

Perfs:


Top	Bot	Thru	Comments
3670	3673		

**INVOICED**  
DATE 6-21-05  
INV. NO. 2005061839

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

RECEIVED  
JUN 21 2005  
KCC WICHITA

Form CR-28