

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00165-00-00
Spot: SW Sec/Twnshp/Rge: 33-21S-32W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: ROLAND GREATHOUSE Well #: 1-33
County: FINNEY Total Vertical Depth: 2750 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

PROD Size: 5.5 feet: 2749 WITH 300 SX CMT
SURF Size: 8.625 feet: 550 WITH 350 SX CMT

89³⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/14/2005 7:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Revd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: RELEASE PKR, POOH W/TBG & PKR, LD SAME, MIRU CEMENTERS, DIG OUT BRADENHEAD, MIX & PUMP 400# COTTON SEED HULLS, PUMP 110 SX CMT, WAIT 30 MINUTES, TOP OFF WITH MUD IF NECESSARY, TIE ONTO 5-1/2" X 8-5/8" ANNULUS, IF ABLE PUMP INTO ANNULUS 50 SX CMT. RDMO. WELD ON CAP, CLEAN UP LOCATION.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 06/14/2005 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 90 SX CMT & 400# HULLS TO 2688'. PRESSURE HELD AT 400#. RAN BOND LO. G AND FOUND TOC @ 1170'. PERFORATE AT 1150'. PUMP 150 SX CMT (50 SX CMT OUTSIDE 5 1/2") AT 1-2 BPM AT 900# TO 200#. NO BLOW OR CIRCULATION UP ANNULUS. HOOKED UP TO 5 1/2" X 8 5/8" ANNULUS & PUMPED 50 SX CMT AT 500#. SURFACE CASING RUPTURED. HAD CMT TO SURFACE ON THE GROUND AROUND THE WELL. 5 1/2" CASING STILL FULL TO SURFACE WITH CMT.

Perfs:


Top	Bot	Thru	Comments
2628	2688		

INVOICED
DATE 6-21-05
INV. NO. 2005061840

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
JUN 21 2005
KCC WICHITA

Form CP-1/5