

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00196-00-00
Spot: NW Sec/Twnshp/Rge: 34-21S-33W
1320 feet from N Section Line, 3960 feet from E Section Line
Lease Name: GANO Well #: 2-34
County: FINNEY Total Vertical Depth: 2712 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

CIBP Size: feet: 1200 WITH 2 SX CMT
CIBP Size: feet: 2550 WITH 2 SX CMT
PROD Size: 5.5 feet: 2711 WITH 300 SX CMT
SURF Size: 8.625 feet: 300 WITH 225 SX CMT

88'4

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/14/2005 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: POOH W/TBG & RODS. MIRU CEMENTERS, PUMP 400# COTTON SEED HULLS, PUMP 110 SX CMT, WAIT 30 MINS. TOP OFF W/MUD IF NECESSARY, TIE ONTO 5-1/2 X 8-5/8" ANNULUS, ATTEMPT TO ESTABLISH PUMP IN, IF ABLE TO, PUMP INTO ANNULUS MIX & PUMP 50 SX CMT, RDMO CEMENTERS, WELD ON CAP, CLEAN UP LOCATION.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2005 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

WELL HAS CASING LEAK. FL @ 450'. SET CIBP @ 2550' WITH 2 SX CMT ON TOP. SET CIBP @ 1200' WITH 2 SX CMT. LOADED HOLE & RAN BOND LOG FROM 1200-750'. NO CMT BEHIND CASING. PERFORATE @ 1040'. PUMPED 150 SX CMT (50 SX CMT OUTSIDE OF CASING) DOWN 5 1/2" CASING AT 2-3 BPM @ 100# - 700#. NO BLOW OR RETURNS OUT 5 1/2" X 8 5/8" ANNULUS. PUMPED 150 SX CMT WITH 400# HULLS IN FIRST 50 SX CMT AT 100# - 600#. BOTH CASING & ANNULUS STAYED FULL.

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2629 | 2686 | | |

INVOICED
DATE 6-21-05
INV. NO. 2005061840

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

JUN 21 2005

KCC WICHITA

[Signature]
Form 27-2/3