

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22612-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 20-34S-13W
807 feet from S Section Line, 540 feet from W Section Line
Lease Name: MEYER Well #: D-2
County: BARBER Total Vertical Depth: 4345 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

CIBP Size: feet: 4030 WITH 2 SX CMT
PROD Size: 4.5 feet: 4324 WITH 115 SX CMT
SURF Size: 10.75 feet: 310 WITH 240 SX CMT

\$141²¹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/06/2005 2:15 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4050' & 2 SX CMT. PLUG AT 690' WITH 50 SX CMT & 15 SX GEL. PLUG AT 330' WITH 70 SX CMT. PLUG AT 40-0' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2005 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4030' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 690' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4082	4092		

INVOICED
DATE 6.21.05
INV. NO. 2005061849

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3300' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JUN 21 2005
KCC WICHITA

Form CR 20