

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21475-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 20-34S-6W  
1551 feet from S Section Line, 4515 feet from E Section Line  
Lease Name: BARRETT Well #: 1  
County: HARPER Total Vertical Depth: 4750 feet

Operator License No.: 32302  
Op Name: KEY GAS CORP.  
Address: 155 N. MARKET - SUITE 900  
WICHITA, KS 67202

PROD Size: 4.5 feet: 4750 100 SX CMT 5050 POZ, 10% SALT  
SURF Size: 8.625 feet: 275 250 SX CMT COMMON, 3% CC

*\$154<sup>38</sup>*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2005 1:00 PM  
Plug Co. License No.: 33436 Plug Co. Name: FORREST ENERGY LIMITED LIABILITY CO  
Proposal Rcvd. from: MIKE MCNAUL Company: KEY GAS CORP. Phone: (620) 474-0162

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/19/2005 5:00 PM KCC Agent: DONALD HOBERECHT

**Actual Plugging Report:**

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Shot casing at 3658' and pulled to surface. Ran 2" tubing to 1202' and spotted 35 sacks of cement. Pulled to 800' and spotted 35 sacks of cement. Pulled to 325' and circulated to surface with 110 sacks of cement. Pulled tubing to surface and topped casing with 20 sacks of cement.

Copeland Acid and Cementing

60/40 posmix with 4% gel

**Perfs:**

Top	Bot	Thru	Comments
4668	4680		
<b>RECEIVED KCC DISTRICT #2 JUN - 6 2005 WICHITA, KS</b>			

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

**INVOICED**  
DATE 6-22-05  
INV. NO. 2005061854

**RECEIVED**  
JUN 22 2005  
KCC WICHITA