

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20202-00-01
Spot: SENESW Sec/Twnshp/Rge: 16-14S-10W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BAKER Well #: 4
County: ELLSWORTH Total Vertical Depth: 3290 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

PROD Size: 4.5 feet: 3200 300 SX CMT
SURF Size: 8.625 feet: 267 150 SX CMT

\$106⁹³

Well Type: EOR UIC Docket No: E16708.4 Date/Time to Plug: 05/05/2005 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Revd. from: GARY SHARP Company: Phone: (316) 262-3596

Proposed Plugging Method: Tubing cemented from 3,000'. Pump 10 sxs. cement to bottom. Perforate casing @ 1,250' and spot 35 sxs. cement. Perforate casing @ 850' and spot 35 sxs. cement. Perforate casing @ 320' and circulate cement to the surface.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/05/2005 5:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Tied onto tubing to pump bottom plug - could not pump down tubing. Perforated at 1,250', 850', & 320'. Ran 1" tubing inside 2 3/8" tubing to 320' & hit bridge - could not work through bridge. Pumped 73 sxs. cement down tubing - well circulated. Ran 1" tubing inside 8 5/8" X 4 1/2" annulus to 320' and circulated 62 sxs. cement to the surface. Checked top plug on 05/06/05 and cement at the surface.

Perfs:

Top	Bot	Thru	Comments
3180	3290		
2807	3094		

Remarks: USED 60/40 POSMIX W?4% GEL BY SWIFT SERVICES, INC. INVOICE # 7786.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 6-22-05
BY 2005061858

RECEIVED
JUN 22 2005
KCC WICHITA