

8-22

6 050007

API NUMBER 15- 065-22,479 0560

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW SW, SEC. 15, T 7 S, R 22 W/E
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5058

Lease Name Nichol Well # 1

Operator: Griggs Oil Inc.
Name & Address: 107 N. Market S
Suite 800
Wichita, Ks. 67202

County Graham 125.94
Well Total Depth 3875 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A
Other well as hereinafter indicated _____

Plugging Contractor R and C Drilling License Number _____
Address Hays, Ks.

Company to plug at: Hour: AM Day: 20 Month: August Year: 19 88

Plugging proposal received from John Wise
(company name) R&C Drilling (phone) _____

were: Order 230 sks 60/40 Poz 6% Gel 3% Cl Cl 1 sk F.C. and
8 5/8 " plug. Spot with drill pipe with no less than 36 vis. mud between all plugs with
good circulation and no fluid loss.

Plugging Proposal Received by Bruce D. Basye
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:30 Day: 22 Month: August Year: 19 88

ACTUAL PLUGGING REPORT
1st plug at 3750 w/25 sks Arbuckle
2nd plug at 1960' w/25 sks Anhydrite
3rd plug at 1150' w/100 sks 1 sk F.C., Dakota
4th plug at 280' w/40 sks
5th plug at 40' w/10 sks
15 sks in rathole 15 sks in mousehole.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
9/16/88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

Signed Bruce D. Basye
(TECHNICIAN)
Bruce D. Basye

DATE 9-22-88

INV. NO. 22363