

6030389

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,681-00-00

NENE SW NE SEC. 15, T. 7 S, R. 22

(WM KLE
6/22/05)

3890
3630 feet from N(S) section line
1495

1650 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6861

Lease Name Nichol Well # 1-B

Operator: Ron's Oil Operations Inc.

County Graham 125.13

Name & Address Box 112 Penokee Ks.

Well Total Depth 3850 feet

67659

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas 67524

Company to plug at: Hour: AM Day: 8 Month: 3 Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) _____

were: 8 5/8 set @ 270.48' w/ 175' of cement. 4 1/2 set @ 3849' w/ 750' of cement.
Perfs. top @ 3464 bottom @ 3636 Recovered 1550' of 4 1/2" casing
with 3 shots. Sun. Cement Company of Hays - Ordered 170' of
50/50 poly 2 gel 3 occ - 40' of gel - 4' of Hulls. 8 5/8 wiper plug.
Woodrock water trucks Morland, Ks.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:AM Day: 8 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Bottom Plug with 4' of com cem. @ TD Sanded

to 3400' w/ 4' of com cem. on top. - Top plug - Pumped down 8 5/8 -
4' of Hulls - 30' of gel, 100' of cement mix. 10' of gel. - 8 5/8 wiper plug
70' of cement mix. Max pressure 200# shut in 150# pressure held.
Plug completed

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1985

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-3-85

INV. NO. 7537

Signed Carl Goodnow
(TECHNICIAN)

3-27-85
10