

4-071191

D-21,727

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-11

API Number: 15-065-21483-00-01

S2 S2 SE /4 SEC. 15, 07 S, 22 W
330 feet from S section line
1320 feet from E section line

Operator license# 5386

Lease: Nichol Well # 2

Operator: Production Drilling, Inc.

County: Graham

Address: 1023 Reservation Road
Hays, Kansas 67601
Larry Patterson

Well total depth 3862 125.51 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 243 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Allied Cementing Company

License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 11 Month: October Year: 1996

Plugging proposal received from: Marty Patterson

Company: Production Drilling, Inc. Phone: 913-625-1189

Were: 8 5/8" - 243' S.P. w/180 sxs cmt. 4 1/2" casing set at 3862' w/175 sxs cement.
Anhy. 1933' - Plug back T.D. 1758' - Casing was squeezed at 1844' with 500 sxs cement - at
1410' with 500 sxs - at 740' with 375 sxs - at 458' with 180 sxs. Pump in with pump truck.
Load 4 1/2" casing with cement top to bottom - shut in under pressure - squeeze 4 1/2" x 8
5/8" annulus with cement. Shut in under pressure. Order 250 sxs 60/40 pozmix - 10% gel -
5 sxs hulls.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M., Day: 11, Month: October, Year: 1996

Actual plugging report: Production Drilling ordered 250 sxs 60/40 pozmix - 10% gel - 5 sxs
hulls. Pumped in with pump truck.

- 1) Annulus cement visable at surface.
- 2) Pumped in 4 1/2" casing with 100 sxs cement followed with 100 sxs cement and 5 sxs hulls added. Max. P.S.I. 500#. S.I.P. 200#.

Remarks: Cemented by Allied Cement Company.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

INVOICED

Marion J. Schmidt (agent)

DATE 10-28-96

INV. NO. 46832

10-11

JAN 06 1997