

15-065-01303-08-01

API NUMBER 15- D-10,296

To: 6 030883
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CNW NE, SEC. 6, T 7 S, R 22 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Mildrexter "B" Well # 2 SWD

Operator: Murfin Drilling Co.
Name &
Address 250 N. Water Ste. 300
Wichita, Ks. 67202

County Graham 134.71
Well Total Depth 4145 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cmt. Co. License Number _____

Address Plainville, Ks.

Company to plug at: Hour: PM Day: 23 Month: 5 Year: 19 87

Plugging proposal received from Pat Canaday

(company name) Murfin Drilling (phone) _____

were: 8 5/8" set at 209 w/160sx 5 1/2 set at 4045 w/125 sx D10296 Perfs

4045 - 4145 open hole Murfin Drlg. Ordered 400 sx.

ATL Cmt. Blend w/6 sx hulls Allied Cmt. Co.

Perf's @ 1987.5' - 88.5' 4 S.P.F. & 1275' - 76' 4 S.P.F.

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 7:PM Day: 23 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT Mix and pump down 5 1/2 82BBL's cmt blend slurry (164 sx) circ.

cmt out braden head. Shut in braden head Pump remained of cement blend w/6 sx

hulls for a total of 400 sx cmt blend or 243 BBL's max PSI 300 # close in

150 # PSI plug complete.

Remarks: Plug checked by Carl G. OK

(If additional description is necessary, use BACK of this form.)

INVOICED (If add'l bill not observe this plugging.)

DATE 7-21-87

INV. NO. 17535

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1987
07-16-87
CONSERVATION DIVISION
WICHITA, KANSAS