

4 060097

6-28

API NUMBER 15- 065-22,580 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NW NW , SEC. 9 , T 7 S, R 22 WXX

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9354

Lease Name Qtee Bank Well # 1

Operator: Central Energy Corporation

County Graham 125.09

Name & Address P.O. Box 47590

Well Total Depth 3849 feet

Wichita, KS 67201

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling License Number 5420

Address Wichita, KS

Company to plug at: Hour: 3:00AM Day: 28 Month: June Year: 19 90

Plugging proposal received from Don Demel

(company name) White & Ellis Drilling (phone) \_\_\_\_\_

were: Order 190 sxs, 60/40 pos 6% gel 1/4 floccel per sx.

Space all plugs with heavy drill mud through drill pipe.

Arbuckle not reached as reported by operator.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXXXX

Operations Completed: Hour: 3:00AM Day: 28 Month: June Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1925' with 25 sxs. Anhydrite 1909-1942'

2nd plug at 1150' with 100 sxs. Dakota 847-1147'

3rd plug at 345' with 40 sxs. Surface pipe to 293'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

Remarks: Allied Cementing  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

JUL - 5 1990  
73-90  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

observe this plugging.

DATE 7-9-90

INV. NO. 28545

*Herb S.*

Signed Herb Deines  
(TECHNICIAN)

Herb Deines