

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED JUN 28 2005 KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: The Warren Corporation

Address: 50 Penn Place, Suite 410, 1900 NW Exp., Oklahoma City, OK 73118-1803

Phone: (405) 843-9393 Operator License #: 33260

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5/5/2005 (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Viola Depth to Top: 4214 Bottom: 4219 T.D. 4219

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-185-23190-000

Lease Name: Suiter

Well Number: 1

Spot Location (QQQQ): C - NE - NE - SW 2310 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 22 Twp. 24 S. R. 15 East West

County: Stafford

Date Well Completed: 7/16/03 9-24-03

Plugging Commenced: 05-03-05

Plugging Completed: 05-10-05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Viola, Oil, 4214, 4219, 8 5/8, 340. Row 2: 5 1/2, 4214, 2640.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set bridge plug 4165', dumped 5 sacks cement, loaded csg with water. Ripped csg at 2820', worked pipe, ripped csg at 2640', pipe came free, pulled csg to 1000', pumped 15 gel, 50 sacks cement, pulled to 390', pumped 50 sacks cement, pulled to 40', pumped 55 sacks. Topped off well with 20 sacks cement.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: The Warren Corporation

State of Oklahoma County, Oklahoma, ss.

John R. Warren (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John R. Warren

(Address) 50 Penn Place, Suite 410, 1900 NW Exp., Oklahoma City, OK 73118

SUBSCRIBED and SWORN TO before me this 20 day of June, 20 05

Sharon Brown Notary Public My Commission Expires: 7/24/06 #02010591

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bu