

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Great Eastern Energy & Development Corp. Address: P.O. Drawer 2436 Midland, TX. 79702 Phone: (432) 682-1178 Operator License #: 9449 Type of Well: D & A Docket #: The plugging proposal was approved on: 6-15-04 by: Herb Deines Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-065-137-20440-00-00 Lease Name: Mulder Well Number: 1 Spot Location (QQQQ): - nw - se - se 990 Feet from [] North / [X] South Section Line 900 Feet from [X] East / [] West Section Line Sec. 27 Twp. 5 S. R. 21 [] East [X] West County: Norton Date Well Completed: na Plugging Commenced: 6-19-05 Plugging Completed: 6-19-05

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: surf, 219, 8 5/8, 219, none.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Total of 225 sks 60/40 6% gel + 1/4 # floeal. 25 sks @ 3578, 25 sks @ 1800, 100 sks. @ 1110, 40 sks. @ 270, 10 sks. @ 40, 15 sks. in RH, 10 sks. in MH.

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 99996 33575 Address: PO Box 31 Russell, KS. 67665

Name of Party Responsible for Plugging Fees: Great Eastern Energy & Development Corp.

State of Kansas County, Norton, ss.

Bill Robinson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Bill Robinson

(Address) Box 2436 Midland TX 79702

SUBSCRIBED and SWORN TO before me this 25 day of June, 2005

Rebecca L. Claycamp Notary Public My Commission Expires: 10-12-06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas



RECEIVED JUN 27 2005 KCC WICHITA

Handwritten signature/initials