

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Murfin Drilling Company, Inc.
 Address: 250 N. Water, Suite 300
 Phone: (316) 267-3241 Operator License #: 30606
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 2/04/05 (Date)
 by: Dave Williams (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
3620-33 Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 147-00528-00-00
 Lease Name: Pinkerton A
 Well Number: #16
 Spot Location (QQQQ): NE - SW - NE -
3630 Feet from North / South Section Line
1650 Feet from East / West Section Line
 Sec. 31 Twp. 5 S. R. 20 East West
 County: Phillips
 Date Well Completed: 9/13/49
 Plugging Commenced: 2/22/05
 Plugging Completed: 2/22/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	196	8 5/8	196	0
	Production	Surface	3662	5 1/2	3662	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/ 2 3/8" tbg to 3600' FS. Swift Services pumped 13 bbl fresh water spacer & 70 sx SMD cmt w/300# hulls. Pulled tbg to 2100' FS & pumped 90 sx cmt w/200# hulls. Cmt to pit. Pulled tbg out of well & hooked to 5 1/2" csg. Pumped 40 sx cmt. Pressured to 550#. Shut in casing w/300#. Hooked to surface pipe & pumped 30 sx cmt at 0#. SI well. Used total of 230 sx.
Witnessed by Dennis Hamel w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
 Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
 State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
 (Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 24th day of June, 2005
Susan Brady My Commission Expires: 11-4-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
[Signature]
JUN 27 2005