

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hartman Oil Co., Inc.
Address: 12950 E. 13th St. N., Wichita, KS 67230-1457
Phone: (620) 277-2511 Operator License #: 30535
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6-28-05 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Hollenberg Depth to Top: 2524 Bottom: 2554 T.D. _____
Herington Depth to Top: 2554 Bottom: 2574 T.D. _____
Krider Depth to Top: 2574 Bottom: 2503 T.D. _____

API Number: 15 - 055-00077-00-00
Lease Name: Brown
Well Number: #1
Spot Location (QQQQ): _____ - SE - NE - SW
1700 Feet from North / South Section Line
2325 Feet from East / West Section Line
Sec. 33 Twp. 21 S. R. 33 East West
County: Finney
Date Well Completed: 1-13-61 2/17/61
Plugging Commenced: 6-22-05
Plugging Completed: 6-28-05
*KCC
Brim
75-05
RBMS
CP 2/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Hollenberg	Gas	2524	2554	8-5/8"	405"	None
Herington	Gas	2554	2574	5-1/2"	2772'	None
Krider	Gas	2574	2603			
Winfield	Gas	2603	2625			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP 5-1/2' set at 2500', 2nd set at 1230', Press cast iron Bridge plug to 500 psi & held, perf @ 1200' mix 225 sks cement, press shut @ 200', mix 200 sks down backside ran press 150 shut in @100,

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 4072
Address: P. O. Box 31-Russell, KS 67665


Name of Party Responsible for Plugging Fees: Hartman Oil Co., Inc.
State of Kansas County, Finney, ss.

Stan Mitchell (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 4550 W. 9 Mile Rd., Garden City, KS 67846

SUBSCRIBED and SWORN TO before me this 30th day of June, 2005
Meryl S. King My Commission Expires: 2/7/2006
Notary Public

Mail to: KCC Conservation Division, 1906 Market - Room 2078, Wichita, Kansas 67202



RECEIVED
JUL 01 2005
KCC WICHITA