

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc.
Address: PO Box 2528 Liberal KS 67905
Phone: (620) 629-4200 Operator License #: 5447
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-10-05 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2976 Bottom: 2942 T.D. 3089
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-067-20514-00-00
Lease Name: Diehl A
Well Number: 2 SE
Spot Location (QQQQ): NE - SE - SE - NW 7-5-05 per Footages
2340 Feet from North / South Section Line
2540 Feet from East / West Section Line
Sec. 11 Twp. 29 S. R. 35 East West
County: Grant
Date Well Completed: 5-5-78
Plugging Commenced: 5-11-05
Plugging Completed: 5-12-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	734	-
				4 1/2	3088	724

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


CIBP + 2sx 2826 to 2806. Loaded 4 1/2 w/mud to 1800, mixed 15sx cmt from 1800 to 1600, mud to 0. Shot & pulled 4 1/2 to 724. Circ. hole w/mud & mixed 50 sx 724 to 574. 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true so help me God.

(Signature) Kenny Andrews
(Address) 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

SUBSCRIBED and SWORN TO before me this 29 day of June, 2005
Anita Peterson My Commission Expires: Oct. 1, 2005
Notary Public



Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202