

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED  
JUL 05 2005  
KCC WICHITA  
Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
Blanks must be Filled

Lease Operator: Oxy USA, Inc.  
Address: PO Box 2528 Liberal KS 67905  
Phone: 620 629-4200 Operator License #: 5447  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 5-17-05 (Date)  
by: Jim Holland (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Council Grove Depth to Top: 2887' Bottom: 2952' T.D. 3090'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-067-20375-00-00  
Lease Name: English C  
Well Number: 2  
Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - SE  
2340 Feet from  North /  South Section Line  
2490 Feet from  East /  West Section Line  
Sec. 20 Twp. 27 S. R. 35  East  West  
County: Grant  
Date Well Completed: 5-8-76  
Plugging Commenced: 5-20-05  
Plugging Completed: 5-20-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	808	-
				4 1/2	3089	1240

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP + 2sx 2830 to 2810. Loaded 4 1/2 w/mud to 1900, mixed 15sx cmt from 1900 to 1700, mud to 0. Shot & pulled 4 1/2 to 825. Circ. hole w/mud & mixed 50 sx 825 to 675. 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905  
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED and SWORN TO before me this 29 day of June, 2005

Anita Peterson My Commission Expires: Oct 1, 2005  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

