

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Citation Oil & Gas Corp.  
Address: P.O. Box 690688; Houston, TX 77269  
Phone: (281) 517-7194 Operator License #: 03553  
Type of Well: Enhr Docket #: E-10,120  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 6/9/2005 (Date)  
by: Herb Deines - confirmed 6/9/2005 (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Topeka Depth to Top: 3071' Bottom: 3131' T.D. 3450'  
LKC Depth to Top: 3238' Bottom: 3366' T.D. 3450'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-04757-00-06  
Lease Name: Wasinger Unit  
Well Number: 18  
Spot Location (QQQQ): \_\_\_\_\_ - NE - NE - SE  
2363 Feet from  North /  South Section Line  
30 Feet from  East /  West Section Line  
Sec. 21 Twp. 11S S. R. 18  East  West  
County: Ellis  
Date Well Completed: 6/1964 10/29/1995  
Plugging Commenced: 6/82005  
Plugging Completed: 6/9/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Topeka	Water	186'	0'	8-5/8"	186'	N/A
LKC	Water	3450'	0'	5-1/2"	3450'	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @3020' KB. Perf'd casing @400' with 4 spf. Mixed and pumped 185 sx "A" down casing

Squeezed to 500#, tied on backside and pumped additional 75 sx "A" down annulus and RD

KCC representative - Case Morris was on location for plugging.

Name of Plugging Contractor: ~~Allied Cementing Co., Inc~~ Mike's Testing & Salvage License #: Unknown 31529  
Address: P.O. Box 31, Russell, KS 67665


Name of Party Responsible for Plugging Fees: Citation Oil & Gas Corp.

State of Harris County, Texas, ss.

Citation Oil & Gas Corp. - Debra Harris (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Debra Harris

(Address) P.O. Box 690688, Houston, Texas 77269-0688



SUBSCRIBED and SWORN TO before me this 13th day of June, 20 05  
Renee Harrell My Commission Expires: 3-2-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
B/W JUN 15 2005  
KCC WICHITA

# ALLIED CEMENTING CO., INC.

16190

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

R

DATE <u>6-9-05</u>	SEC <u>21</u>	TWP <u>11S</u>	RANGE <u>18W</u>	CALLED OUT	ON LOCATION	JOB START <u>11:30 AM</u>	JOB FINISH <u>12:30 PM</u>
LEASEL <u>WASINGER</u> WELL # <u>#18</u>			LOCATION <u>HAYS N TO RIVER 1W</u>			COUNTY <u>ELLIS</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<u>15 1/2 SEC</u>				

CONTRACTOR <u>MILES</u>	OWNER
TYPE OF JOB <u>DTA</u>	
HOLE SIZE	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT  
AMOUNT ORDERED 200 60/40 10% GEL

COMMON	<u>120</u>	@	<u>8<sup>th</sup></u>	<u>1044<sup>o</sup></u>
POZMIX	<u>80</u>	@	<u>4<sup>th</sup></u>	<u>376<sup>o</sup></u>
GEL	<u>20</u>	@	<u>14<sup>th</sup></u>	<u>280<sup>o</sup></u>
CHLORIDE		@		
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING		@		<u>352</u>
MILEAGE				<u>567</u>
TOTAL				<u>2619</u>

### EQUIPMENT

PUMP TRUCK # <u>777</u>	CEMENTER <u>MARK</u>	HELPER <u>PAUL</u>
BULK TRUCK # <u>282</u>	DRIVER <u>FRONT</u>	
BULK TRUCK #	DRIVER	

### REMARKS:

MAX 125 SK DOWN 5 1/2  
MAX 1100<sup>o</sup> SHUT IN 400<sup>o</sup>

MAX 75 SK DOWN BACKSIDE  
MAX 500<sup>o</sup>  
SHUT IN 150

CHARGE TO: MILES TESTING  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

### SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>600<sup>o</sup></u>
EXTRA FOOTAGE	@		
MILEAGE	<u>43</u>	@	<u>5<sup>o</sup></u>
		@	
		@	
TOTAL			<u>815<sup>o</sup></u>

RECEIVED

JUN 15 2005

KCC WICHITA

TOTAL 815<sup>o</sup>

### PLUG & FLOAT EQUIPMENT

MANIFOLD	@		
	@		
	@		
	@		